

Cornerstone Vocational Training Ltd

Risk Assessment

Reference: K02

Title	Basic plumbing	Date Of Assessment	Thu 04 Sep 2025
Site	Cornerstone Wirral	Location	70 Price Street
Risk Assessor	Brendan Bell	Assisted By	-
Non-Employees Involved	-	People At Risk	Visitors, Children & Young Persons, Service Users, Employees
Task Description	Fitting a full bathroom suite		
Review Date	Thu 03 Sep 2026	Reviewer	Brendan Bell

Hazards

Hazard	Manual handling
Risk Of Harm	Incorrect lifting could cause musculoskeletal injuries. The toilet and sink if dropped could cause a crush injury or if smashed a laceration.
Existing Control Measures	1. Lift in pairs and use the correct manual handling techniques, keep back straight, bend knees and keep the object close to your body. 2. Place all the equipment on the impact matting provided to reduce the risk of breaking the porcelain sink and toilet. 3. Use the correct PPE throughout the task of fitting the bathroom

Hazard	Uneven, Wet or Slippery Floors
Risk Of Harm	Once the waste and water feed have been fitting learners will test for leaks. This can cause wet surfaces and become a potential slip hazard.
Existing Control Measures	1. Use non slip impact mats around the area being checked for leaks. 2. Mop up any spillages and leaks as soon as they become apparent. 3. Large leaks/spillages should be soaked up with sawdust generated by the chop saw. 4. Maintain a clean & tidy area throughout the fitting of the bathroom.